




**NOTE:**  
ORDER DOORS BY CLEAR  
OPENING DIMENSIONS  
REQUIRED




**1 FLOOR PLAN VIEW**  
SCALE: 1:15 MTS.



**2 FRONT ELEVATION VIEW**  
SCALE: 1:15 MTS.



**3 3D VIEW**  
SCALE: N.T.S.



**4 SIDE ELEVATION VIEW**  
SCALE: 1:15 MTS.

**ulti group**

© Ulti Group Ltd, 2020

**NOTE:**  
CONTACT ULTI GROUP FOR ANY  
CUSTOMISATIONS AND TO DISCUSS  
PROJECT SPECIFIC INFORMATION

www.ultigroup.co.nz  
sales@ultigroup.co.nz  
Phone: 0800 807 753  
105 Glover Road, Hawera, 4610

**SPECIFICATIONS :**

RELEASED VERSION NO. : **VERSION 1**

PRODUCT GROUP : **HIGH SPEED DOORS**

STOCK CODE : **00000**

APPLICATION : **INTERNAL & EXTERNAL**

STANDARD SIZE : **4000 mm WIDE x 4000 mm HIGH**

MINIMUM SIZE : **1500 mm WIDE x 1500 mm HIGH**

MAXIMUM SIZE : **6000 mm WIDE x 6000 mm HIGH**

HEADROOM : **900 mm >4000 mm H or  
1300 mm >6000 mm**

SIDE ROOM - MOTOR SIDE : **400 mm**

SIDE ROOM - NON MOTOR SIDE : **400 mm**

STANDARD FRAME MATERIAL : **GALVANISED STEEL**

STANDARD FRAME COLOUR : **GALVANISED FINISH**

STANDARD CURTAIN MATERIAL : **ALUMINIUM**

CURTAIN COLOUR (INSIDE / OUTSIDE) : **RAL 9006 / RAL 9006**

VISION PANELS : **OPTIONAL**

POWER SUPPLY : **3 PHASE, 400V + NEUTRAL  
+ EARTH 15 Amp**

**TITLE:**  
**ULTI SPIRAL PLUS DOOR**

**SHEET NO. :** 1 OF 1  
**DATE :** AUG. 17, 2020

**DRAWING NUMBER :**  
**SPIRAL-PLUS-001**

**APPROVED BY :** -  
**DRAWN BY :** J.ENRIQUEZ

**SCALE :** As indicated  
**SHT. SIZE :** A0

\*All dimensions are in millimeters unless otherwise specified