



1 FRONT ELEVATION VIEW
SCALE: 1:15 MTS.


NOTE:
ORDER DOORS BY CLEAR
OPENING DIMENSIONS
REQUIRED



2 FLOOR PLAN VIEW
SCALE: 1:15 MTS.



3 SIDE ELEVATION VIEW
SCALE: 1:15 MTS.



4 3D VIEW
SCALE: N.T.S.

END USER :	BUILDING NAME
DOOR REFERENCE :	00000
VERSION NO. :	VERSION 1
PRODUCT GROUP :	HIGH SPEED DOORS
STOCK CODE :	00000
APPLICATION :	INTERNAL or EXTERNAL
* CLEAR OPENING HEIGHT :	4000 mm
* CLEAR OPENING WIDTH :	4000 mm
* HEADROOM :	900 mm
* SIDE ROOM - MOTOR SIDE :	400 mm
* SIDEROOM - NON MOTOR SIDE :	400 mm
FRAME MATERIAL :	GALVANISED STEEL
* FRAME COLOUR :	GALVANISED FINISH
CURTAIN MATERIAL :	ALUMINIUM
* CURTAIN COLOUR INSIDE :	RAL 9006 - WHITE ALUMINIUM
* CURTAIN COLOUR OUTSIDE :	RAL 9006 - WHITE ALUMINIUM
* VISION PANEL :	NO
BOTTOM OF VISION :	N / A
TOP OF VISION :	N / A
BOTTOM OF VENTILATED :	N / A
TOP OF VENTILATED :	N / A
MOTORISATION :	IP54 RATED 3 PHASE MOTOR DRIVE & ELECTROMAGETIC BRAKE
MOTOR POSITION :	RIGHT HAND - INSIDE MOUNT
CONTROL PANEL :	RIGHT HAND - METAL BOX
EXTRA CONTROL PANEL CABLE LENGTH :	N / A
* POWER SUPPLY :	3 PHASE, 400V + NEUTRAL + EARTH 15 Amp - RIGHT SIDE
HEATING POWER SUPPLY :	N / A
* ACTIVATION INSIDE :	PUSH BUTTON & EMERGENCY STOP BUTTON
* ACTIVATION OUTSIDE :	PUSH BUTTON & EMERGENCY STOP BUTTON
* OPTIONAL ACTIVATION :	
* OPTIONAL SAFETY:	
* OPTIONAL EMERGENCY EGRESS:	NONE
* WALL TYPE :	CONCRETE WALL
* WALL THICKNESS :	200 mm THICK
* PIGGYBACK FRAME :	N / A
* OPTIONAL SELECTIONS:	<input type="checkbox"/> PRINTED LOGO <input type="checkbox"/> FULL PRINTED CURTAIN <input type="checkbox"/> WINDLOAD UPGRADE

ulti
group

© Ulti Group Ltd, 2020

NOTE:

CONTACT ULTI GROUP FOR ANY
CUSTOMISATIONS AND TO DISCUSS
PROJECT SPECIFIC INFORMATION

www.ultigroup.co.nz
sales@ultigroup.co.nz
Phone: 0800 807 753
105 Glover Road, Hawera, 4610

CLIENT APPROVAL : (PLEASE CHECK & APPROVE
THE FOLLOWING POINTS)

- ☐ POWER SUPPLY REQUIREMENT
☐ POWER SUPPLY LOCATION
☐ CLEAR OPENING DIMENSION ' WIDTH & HEIGHT '
☐ SIDE ROOM CLEARANCE ' LEFT & RIGHT '
☐ HEADROOM CLEARANCE
☐ COLOURS (FRAME & CURTAIN)
☐ WINDOWS / VISION
☐ MOUNTING SURFACES
☐ ACTIVATIONS
☐ EXTRA e.g. SAFETY FEATURES, ETC.

SIGNED

NAME :

POSITION :

DATE :

REVISIONS			
REV.	DESCRIPTION	BY	DATE
1	-	SP	AUG. 18, 2020

TITLE:

ULTI SPIRAL PLUS DOOR

PROJECT CLIENT:

CLIENT NAME

ULTI PROJECT REFERENCE NO. :
00000

SHEET NO. :
1 OF 1

DATE :
AUG. 18, 2020

DRAWING NUMBER :

SPIRAL-PLUS-001

APPROVED BY : J.PRESTIDGE

DRAWN BY : J.ENRIQUEZ

SCALE : As indicated SHT. SIZE : A0

*All dimensions are in millimeters unless otherwise specified